BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

(122)

NEGOTIATED SCHEDULE - B

Drilling of Borewells, Installation of Pump and motors, Providing Pipeline and additional motor pumps and necessary accessories to existing borewells in ward no.06

SNo	Quantity	Item Name	Unit	Negotiated Rates quoted by M/s SATHYA BOREWELL CLEANING	
				In figures	In words
1	41.00	Geophysical investigation of site for sinking borewell for supplying drinking water to the habitation either through the hand pump, MWS or P.W.S.S. by vertical electrical sounding by adopting venner or schlumbergers's method, including reconnaissance survey of geological formation, Geological investigation of existing ground water in vicinity, its quality, quantity & acceptability of the users indicating the location of site, recommended depth of casing pipe required to seal the top unconsolidated formation including an extra depth of 1.0 mtr in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site, engaging technical personal and labour required etc	Each BW	4228.39	Rupees Four Thousand Two Hundred Twenty Eight And Paise Thirty Nine Only
2	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 0 to 50 m	Rmtr	389.40	Rupees Three Hundred Eighty Nine And Paise Forty Only
3	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 50 to 100 m	Rmtr	496.01	Rupees Four Hundred Ninety Six And Paise One Only
4	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 100 to 150 m	Rmtr	511.72	Rupees Five Hundred Eleven And Paise Seventy Two Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by M/s SATHYA BOREWELL CLEANING	
				In figures	In words (2)
5	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 150 to 200 m	Rmtr	601.49	Rupees Six Hundred One And Paise Forty Nine Only
6	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 200 to 250 m	Rmtr	711.47	Rupees Seven Hundred Eleven And Paise Forty Seven Only
7	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 250 to 300 m	Rmtr	785.53	Rupees Seven Hundred Eighty Five And Paise Fifty Three Only
8	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 300 to 350 m	Rmtr	925.80	Rupees Nine Hundred Twenty Five And Paise Eighty Only
9	2050.00	Sinking of borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above 900 CMF & above in all strata including over budern upto 20 m. fixing of casing pipes, collars & cap with necessary cutting, threading & welding including transportation of rig and supporting vehicle, crew charges & cost of consumables etc., complete including yield testing at the final depth with minimum working of compressor for one hour(excluding cost of casing pipes, collars, cap etc.,) 350 to above	Rmtr	1009.97	Rupees One Thousand Nine And Paise Ninety Seven Only
10	2460.00	Supplying of ISI Mark 175 mm nominal bore medium black ERW casing pipe of 5mm thick black electric resistance continous welded midle steel tube material confirming to IS 1387/1993 and manufactured from hot rolled steel skelp/stripes in random length of 4 to 7 mtr both ends threaded confirming to IS 554/1985 one end(including of all taxes)	Rmtr	1486.90	Rupees One Thousand Four Hundred Eighty Six And Paise Ninety Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by M/s SATHYA BOREWELL CLEANING	
				In figures	In words
11	410.00	Providing and fixing 250mm dia PVC pipe and as per specification and directions.	Rmtr	1518.32	Rupees One Thousand Five Hundred Eighteen And Paise Thirty Two Only
12	41.00	175 mm dia M.S. Casing cap	Each	112.22	Rupees One Hundred Twelve And Paise Twenty Two Only
13	410.00	M.S. Casing pipe collars 'C' Class	Each	168.33	Rupees One Hundred Sixty Eight And Paise Thirty Three Only
14	902000.00	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc,. complete box of 21600 sq cm	Sqm	0.36	Rupees And Paise Thirty Six Only
15	2050.00	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m)	Each	100.23	Rupees One Hundred And Paise Twenty Three Only
16	123.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	No	254.94	Rupees Two Hundred Fifty Four And Paise Ninety Four Only
17	1435.00	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554)	Mtr	152.97	Rupees One Hundred Fifty Two And Paise Ninety Seven Only
18	1435.00	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces	Mtr	127.47	Rupees One Hundred Twenty Seven And Paise Forty Seven Only
19	82.00	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	320.94	Rupees Three Hundred Twenty And Paise Ninety Four Only
20	41.00	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia	No	4703.37	Rupees Four Thousand Seven Hundred Three And Paise Thirty Seven Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by M/s SATHYA BOREWELL CLEANING	
				In figures	In words
21	41.00	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No	305.06	Rupees Three Hundred Five And Paise Six Only
22	41.00	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No	329.03	Rupees Three Hundred Twenty Nine And Paise Three Only
23	10.00	Cleaning of bore well inciuding yield tetsting of borewell either using slow or fast rig for not more than 2 hours at the final depth with air compressor or suitable pump as per specification (PRED 12-13 SL NO.9.5 PAGE NO.49)	Each	11034.46	Rupees Eleven Thousand Thirty Four And Paise Forty Six Only
24	41.00	Borewell Clamp Set	Set	1961.10	Rupees One Thousand Nine Hundred Sixty One And Paise Ten Only
25	30.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 17.5HP 30 Stage	No	78581.28	Rupees Seventy Eight Thousand Five Hundred Eighty One And Paise Twenty Eight Only
26	21.00	Supply & delivery at site brand new texmo/innoval/lubi/sabar /Atalanta/calamal/ waterman/Radha make suitable HP deep well submercible pumpset suitable for vertical installation in 150 dia borewells compressing of single stage or multistage CF pump close coupled by means of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water squirrel cagesubmercible induction motor suitable for operation of 3Ph, 50Hz.380/440 volts AC supply fitted with required accessories such as suction, casing, suction strainers, sand guard. Non return valve etc Complete the pump and motor shall from an integral unit with all the required fittings 20 HP 40 Stage	Rmtr	98703.25	Rupees Ninety Eight Thousand Seven Hundred Three And Paise Twenty Five Only
27	17085.00	Providing, laying & jointing GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings) 50mm dia GI pipe B Class	No	452.14	Rupees Four Hundred Fifty Two And Paise Fourteen Only
28	2296.00	Supply and fixing Heavy Collar for GI Pipes 50MM	Mtr	196.11	Rupees One Hundred Ninety Six And Paise Eleven Only
29	35700.00	Supplying of submersible pump cable 1X3X6..0 Sq.mm	No	156.89	Rupees One Hundred Fifty Six And Paise Eighty Nine Only

Contractor

	Quantity	Item Name	Unit	Negotiated Rates quoted by M/s SATHYA BOREWELL CLEANING	
				In figures	In words 118
30	46.00	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc,. completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above Up to 20HP with star delta starter (MR)	No	22879.50	Rupees Twenty Two Thousand Eight Hundred Seventy Nine And Paise Fifty Only
31	41.00	Supplying & delivery of brand 50mm Gate Valve.	No	1961.10	Rupees One Thousand Nine Hundred Sixty One And Paise Ten Only
32	41.00	Supplying & delivery of brand 50mm Non Return Valve.	No	1961.10	Rupees One Thousand Nine Hundred Sixty One And Paise Ten Only
33	41.00	Supplying and fixing MCB	No	980.55	Rupees Nine Hundred Eighty And Paise Fifty Five Only
34	6420.60	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications	Cum	345.31	Rupees Three Hundred Forty Five And Paise Thirty One Only
35	14268.00	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete	Mtr	429.61	Rupees Four Hundred Twenty Nine And Paise Sixty One Only
36	6420.60	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications	Cum	139.74	Rupees One Hundred Thirty Nine And Paise Seventy Four Only

Contractor